

\*\*\*\*\*  
EG&G ISC ISC-ES 31 63 29.00 99 (January 2009)  
-----  
Preparing Activity: EG&G ISC-ES (NEW)

EG&G ISC GUIDE SPECIFICATIONS

References are in agreement with UMRL dated January 2009

\*\*\*\*\*

SECTION TABLE OF CONTENTS

DIVISION 31 - EARTHWORK

SECTION 31 63 29.00 99

DRILLED CONCRETE PIERS AND SHAFTS

01/09

PART 1 GENERAL

1.1 UNIT PRICES

1.1.1 Basis of Bids

1.1.2 Tests

1.1.2.1 Load Test

1.1.2.2 Penetration Test

1.1.2.3 Proof Test Hole

1.1.3 Separate Unit Prices

1.1.3.1 Additional Concrete Pier or Shaft Lengths

1.1.3.2 Omitted [Pier] [and] [Shaft] Lengths

1.1.3.3 Casings Permanently Left in Place

1.1.3.4 Reinforcing Steel for Additional [Piers] [Shafts]

1.1.3.5 Reinforcing Steel for [Piers] [Shafts] Omitted

1.1.3.6 Removal of Rock

1.1.3.7 Removal of Obstructions Other Than Rock

1.1.4 Basis Of Payment

1.1.4.1 Unit Price

1.1.4.2 Full Compensation

1.1.4.3 Load Tests

1.1.4.4 Penetration Tests

1.1.4.5 Proof Test Holes

1.2 REFERENCES

1.3 SUBMITTALS

1.4 QUALITY ASSURANCE

1.4.1 General

1.4.2 Sequencing and Scheduling

1.4.3 Drilling and Excavation Equipment

1.4.4 Construction Criteria

1.4.5 Inspection Criteria

1.4.6 Qualification of Excavation Contractor

1.4.7 Qualification of Professional Engineer

1.4.8 Welding Qualifications

1.4.9 Pre-Construction Conference

1.5 PROJECT CONDITIONS

1.5.1 Existing Conditions

1.5.2 Interruption of Existing Utilities

1.5.3 Weather Limitations

PART 2 PRODUCTS

- 2.1 STEEL REINFORCEMENT
  - 2.1.1 Deformed Steel Bars
  - 2.1.2 Plain Steel Wire
- 2.2 READY-MIX CONCRETE

PART 3 EXECUTION

- 3.1 PREPARATION
- 3.2 REQUIRED TEST REPORTS
- 3.3 EXCAVATION
- 3.4 STEEL REINFORCEMENT
- 3.5 CONCRETE PLACEMENT
- 3.6 FIELD TESTING

-- End of Section Table of Contents --

\*\*\*\*\*  
EG&G ISC ISC-ES 31 63 29.00 99 (January 2009)  
-----

Preparing Activity: EG&G ISC-ES (NEW)

### EG&G ISC GUIDE SPECIFICATIONS

References are in agreement with UMRL dated January 2009

\*\*\*\*\*

## SECTION 31 63 29.00 99

### DRILLED CONCRETE PIERS AND SHAFTS 01/09

\*\*\*\*\*

NOTE: This guide specification covers the requirements for the procurement, installation, and testing of drilled concrete piers and shafts.

Edit this guide specification for project specific requirements by adding, deleting, or revising text. For bracketed items, choose applicable items(s) or insert appropriate information.

Remove information and requirements not required in respective project, whether or not brackets are present.

Comments and suggestions on this guide specification are welcome and should be directed to the technical proponent of the specification at ISC-ES.

\*\*\*\*\*

## PART 1 GENERAL

\*\*\*\*\*

NOTE: Use the following specifications in conjunction with this section:

SECTION 00 22 13 SUPPLEMENTARY INSTRUCTIONS TO  
BIDDERS

SECTION 01 35 29 SAFETY AND OCCUPATIONAL HEALTH  
REQUIREMENTS

NOTE: On the drawings, show:

1. Subsurface-soil-data logs.
2. Top and bottom elevation of each drilled pier and/or shaft.
3. Size (diameter in mm inches, bearing capacity, and total number of each size of drilled pier and/or shaft..
4. Dimensions of the bell, if required.

5. Dimensions of the casing.
6. Reinforcing steel details, if required.
7. Location of drilled piers and/or shafts to be penetration tested, if required.
8. Location of drilled piers and/or shafts to be proof tested, if required.
9. Locations, size, and installation sequence of load testing drilled pier and/or shaft, if required.

\*\*\*\*\*

#### [1.1 UNIT PRICES

\*\*\*\*\*

NOTE: Delete this subpart for NASA projects.

\*\*\*\*\*

- a. Requirements for price breakdown of drilled concrete piers or shafts are specified in Section 01 20 00.00 20 PRICE AND PAYMENT PROCEDURES. Requirements for construction scheduling related to drilled concrete piers or shaft work are specified in Section 01 32 17.00 20 NETWORK ANALYSIS SCHEDULES.

\*\*\*\*\*

NOTE: If requirements for price breakdown of drilled pier and/or shaft work are specified in Section 01 22 00.00 10 MEASUREMENT AND PAYMENT, use the following paragraph and delete subparts 1.2.1 through 1.2.4.

\*\*\*\*\*

- b. Requirements for price breakdown of drilled concrete piers or shaft work are specified in Section 01 22 00.00 10 MEASUREMENT AND PAYMENT.

\*\*\*\*\*

NOTE: This paragraph anticipates bids on a lump sum price for an entire project including drilled concrete piers or shaft work with directed changes being in accordance with the CONTRACT CLAUSES or in accordance with unit prices as defined in paragraph "Separate Unit Prices."

Delete "in accordance with the CONTRACT CLAUSES" or paragraphs "Tests" and "Separate Unit Prices" for lump sum projects.

\*\*\*\*\*

##### [1.1.1 Basis of Bids

Base the bid on the number and total length of drilled concrete [piers] [and] [shafts], established by top and bottom elevations and diameters, as indicated and specified. Adjustment of the contract will be made [in accordance with the CONTRACT CLAUSES], if the total length of drilled

concrete piers or shafts installed and approved is greater or less than the total length shown. The Contractor will not receive payment for rejected concrete piers or shafts or for those not conforming to specifications.

] [1.1.2 Tests

1.1.2.1 Load Test

The Contract includes [\_\_\_\_\_] load tests rated at [\_\_\_\_\_] metric ton ton per drilled concrete [pier] [or] [shaft]. The Contracting Officer reserves the right to increase or decrease the number of load tests. Adjustments in the contract price will be made for each such increase or decrease by the amount bid for "Additional Drilled Concrete [Pier] [or] [Shaft] Test" or "Omitted Drilled Concrete [Pier] [or] [Shaft] Load Test".

1.1.2.2 Penetration Test

The Contract includes [\_\_\_\_\_] penetration tests. The Contracting Officer reserves the right to increase or decrease the number of penetration tests. Adjustments in the contract price will be made for each such increase or decrease by the amount bid for "Additional Penetration Test" or "Omitted Penetration Test".

1.1.2.3 Proof Test Hole

The Contract includes [\_\_\_\_\_] proof test holes. The Contracting Officer reserves the right to increase or decrease the number of proof test holes. Adjustments in the contract price will be made for each such increase or decrease by the amount bid for "Additional Proof Test Hole" or "Omitted Proof Test Hole".

] [1.1.3 Separate Unit Prices

1.1.3.1 Additional Concrete Pier or Shaft Lengths

Additional [pier] [shaft] lengths will be paid for at the contract unit price for "Additional Caisson Length" for each diameter of [pier] [shaft] installed as approved.

1.1.3.2 Omitted [Pier] [and] [Shaft] Lengths

The contract price will be reduced by the amount bid for "Omitted [Pier] [Shaft] Length" for each diameter of [pier] [shaft] omitted as directed.

1.1.3.3 Casings Permanently Left in Place

Steel casings permanently left in place due to contract conditions:

- a. Total pounds of steel beyond casings indicated will be paid for at the contract unit price per pound for "Additional Steel Casing."
- b. Omitted Casing Steel: The contract price will be reduced by the amount bid for "Omitted Casing Steel" omitted as directed.

1.1.3.4 Reinforcing Steel for Additional [Piers] [Shafts]

Reinforcing steel for additional [pier] [shaft] lengths will be paid for at the contract unit price for "Additional [Pier] [Shaft] Reinforcing Steel" installed as approved.

#### 1.1.3.5 Reinforcing Steel for [Piers] [Shafts] Omitted

The contract price will be reduced by the amount bid for "Omitted [Pier] [Shaft] Reinforcing Steel" omitted as directed.

#### 1.1.3.6 Removal of Rock

Removal of rock within the limit of [piers] [shafts] will be paid for at the contract unit price for "Removal of Rock" per linear meter foot, for each diameter of caisson installed. Rock excavation is defined as any hard dense material that cannot be removed with [pier] [shaft] drilling equipment having the specified capacity and could only be removed by hand, air tools, blasting, or other specialized methods.

#### 1.1.3.7 Removal of Obstructions Other Than Rock

Removal of obstructions other than rock within the limits of the [piers] [shafts] which cannot be removed using standard drilling equipment with the specified capacity will be paid for at the contract unit price per linear meter foot for "Removal of Obstructions" for each diameter of [pier] [shaft] installed.

#### ] 1.1.4 Basis Of Payment

\*\*\*\*\*  
NOTE: Where the basis for bidding is based entirely  
on unit price, subpart 1.2.1 through 1.2.3 should be  
deleted and the subparts 1.2.4.1 through 1.2.4.5  
substituted.  
\*\*\*\*\*

#### 1.1.4.1 Unit Price

The Contracting Officer has the right to increase or decrease the total length linear footage of drilled [piers] [shafts] to be furnished and installed by changing the [pier] [shaft] elevations, by requiring the installation of additional [piers] [shafts], or omission of [piers] [shafts] from the requirements shown and specified. Whether or not such changes are made, the Contractor will be paid at the contract unit price per linear meter foot (including drilled pier and/or shaft) multiplied by the total linear meters feet of acceptable [piers] [shafts] actually installed provided, however, that in the event the Contracting Officer requires an increase or decrease in the total length linear footage of caissons furnished and installed, the contract unit price will be adjusted in accordance with the CONTRACT CLAUSES.

#### 1.1.4.2 Full Compensation

Payment in accordance with the above paragraph Unit Price constitutes full compensation for furnishing, delivering, handling, and/or installing (as applicable) all material, labor and equipment necessary to meet contract requirements applicable to the [piers] [shafts]. The Contractor will not be allowed payment for rejected [piers] [shafts].

#### 1.1.4.3 Load Tests

The Contract includes [\_\_\_\_\_] [\_\_\_\_\_] -ton [pier] [shaft] load tests. The Contracting Officer reserves the right to increase or decrease the number

of load tests. Adjustments in the contract price will be made for such increases or decreases by the amounts bid for "Additional [Pier] [Shaft] Load Test" or "Omitted [Pier] [Shaft] Load Test."

#### 1.1.4.4 Penetration Tests

The Contract includes [\_\_\_\_\_] penetration tests. The Contracting Officer reserves the right to increase or decrease the number of penetration tests. Adjustments in the contract price will be made for such increases or decreases by the amounts bid for "Additional Penetration Test" or "Omitted Penetration Test."

#### 1.1.4.5 Proof Test Holes

The Contract includes [\_\_\_\_\_] proof test holes. The Contracting Officer reserves the right to increase or decrease the number of proof test holes. Adjustments in the contract price will be made for such increases or decreases by the amounts bid for "Additional Proof Test Hole" or "Omitted Proof Test Hole."

### ]1.2 REFERENCES

\*\*\*\*\*

NOTE: This paragraph is used to list the publications cited in the text of the guide specification. The publications are referred to in the text by basic designation only and listed in this paragraph by organization, designation, date, and title.

Use the Reference Wizard's Check Reference feature when you add a RID outside of the Section's Reference Article to automatically place the reference in the Reference Article. Also use the Reference Wizard's Check Reference feature to update the issue dates.

References not used in the text will automatically be deleted from this section of the project specification when you choose to reconcile references in the publish print process.

\*\*\*\*\*

The publications listed below form a part of the Project Specifications and are a component to the requirements for the work contained in this Section.

#### ACI INTERNATIONAL (ACI)

ACI 117	(2006) Standard Specifications for Tolerances for Concrete Construction and Materials
ACI 301	(2005; Errata 2008) Specifications for Structural Concrete
ACI 304R	(2000) Guide for Measuring, Mixing, Transporting, and Placing Concrete
ACI 305R	(1999; Errata 2006) Hot Weather Concreting

ACI 306.1	(1990; R 2002) Standard Specification for Cold Weather Concreting
ACI 318/318R	(2008; Errata 2008) Building Code Requirements for Structural Concrete and Commentary
ACI 336.1	(2001) Specification for the Construction of Drilled Piers
ACI SP-66	(2004) ACI Detailing Manual

#### AMERICAN SOCIETY OF CIVIL ENGINEERS (ASCE)

ASCE/SEI 7-05	(2006) Minimum Design Loads for Buildings and Other Structures, Including Supplement No. 1
---------------	--

#### AMERICAN WELDING SOCIETY (AWS)

AWS A5.1/A5.1M	(2004; Errata 2004) Carbon Steel Electrodes for Shielded Metal Arc Welding
AWS D1.1/D1.1M	(2008) Structural Welding Code - Steel
AWS D1.4/D1.4M	(2005; Errata 2005) Structural Welding Code - Reinforcing Steel

#### ASTM INTERNATIONAL (ASTM)

ASTM A 615/A 615M	(2008b) Standard Specification for Deformed and Plain Carbon-Steel Bars for Concrete Reinforcement
ASTM A 82/A 82M	(2007) Standard Specification for Steel Wire, Plain, for Concrete Reinforcement
ASTM C 143/C 143M	(2008) Standard Test Method for Slump of Hydraulic-Cement Concrete
ASTM C 150	(2007) Standard Specification for Portland Cement
ASTM C 172	(2008) Standard Practice for Sampling Freshly Mixed Concrete
ASTM C 31/C 31M	(2008a) Standard Practice for Making and Curing Concrete Test Specimens in the Field
ASTM C 39/C 39M	(2005e1e2) Standard Test Method for Compressive Strength of Cylindrical Concrete Specimens
ASTM C 94/C 94M	(2007) Standard Specification for Ready-Mixed Concrete



CONCRETE REINFORCING STEEL INSTITUTE (CRSI)

CRSI 1MSP (2003) Manual of Standard Practice, (27th Ed)

U.S. FEDERAL HIGHWAY ADMINISTRATION (FHWA)

FHWA-IF-99-025 (2000) Drilled Shafts: Construction Procedures and Design Methods with (Errata Sheet)

FHWA-IP-84-11 (1984) Handbook on Design and Construction of Drilled Shafts under Lateral Load

U.S. NATIONAL ARCHIVES AND RECORDS ADMINISTRATION (NARA)

29 CFR 1926.501 Duty To Have Fall Protection

29 CFR 1926.502 Fall Protection Systems Criteria and Practices

29 CFR 1926.651 Specific Excavation Requirements

1.3 SUBMITTALS

\*\*\*\*\*

NOTE: Review submittal description (SD) definitions in Section 01 33 00 SUBMITTAL PROCEDURES and edit the following list to reflect only the submittals required for the project. Submittals should be kept to the minimum required for adequate quality control.

A "G" following a submittal item indicates that the submittal requires Government approval. Some submittals are already marked with a "G". Only delete an existing "G" if the submittal item is not complex and can be reviewed through the Contractor's Quality Control system. Only add a "G" if the submittal is sufficiently important or complex in context of the project.

For submittals requiring Government approval on Army projects, a code of up to three characters within the submittal tags may be used following the "G" designation to indicate the approving authority. Codes for Army projects using the Resident Management System (RMS) are: "AE" for Architect-Engineer; "DO" for District Office (Engineering Division or other organization in the District Office); "AO" for Area Office; "RO" for Resident Office; and "PO" for Project Office. Codes following the "G" typically are not used for Navy, Air Force, and NASA projects.

Choose the first bracketed item for Navy, Air Force and NASA projects, or choose the second bracketed item for Army projects.

\*\*\*\*\*

Submit the following in accordance with Section 01 33 00 SUBMITTAL PROCEDURES:

#### SD-02 Shop Drawings

Installation drawings are to include, but not limited to, the following items indicating a completely dimensioned layout and location of drilled shafts and concrete placement for foundation system:

- Drilled shaft diameters
- Depth of test holes
- Top and Bottom of shaft elevations
- Steel Reinforcement
- Anchor bolt locations
- Accessories

#### SD-05 Design Data

As applicable submit the following:

Submit a drilled shaft foundation design analysis to include, but not limited to the following:

- Applicable Building code criteria for the geographic area where the excavation will take place
- Dead and Live Loads
- Compressive and Lateral Loads
- Collateral Loads
- Foundation Loads
- Bearing strata
- Casing description

Submit Mix design data in accordance with the paragraph entitled, "Ready-Mix Concrete".

#### SD-06 Test Reports

Submit test reports in accordance with the test described in paragraph entitled, "Field Testing" for the following items:

- Soils Report
- Ground Water conditions
- Load Test
- Penetration Test
- Slump
- Concrete
- Compressive Strength

#### SD-07 Certificates

\*\*\*\*\*  
NOTE: Specify load tests when needed to confirm design capacities. At least one caisson location should be load tested in each area of substantially different subsoil conditions. Indicate number, size, and location of test caisson and sequence.  
\*\*\*\*\*

Submit certificates for the following items showing conformance with referenced standards contained in this section:

Bill of Lading for "Ready-Mix Concrete" deliveries  
"Ready-Mix Concrete"  
Steel Reinforcement  
Welding Certificates  
Excavation and Drilling Equipment

**Qualifications of Excavator**

Certify that the excavator meets requirements specified under paragraph entitled "Qualifications of Excavation Contractor".

**Qualifications of Engineer**

Certify that the engineer meets requirements specified under paragraph entitled "Qualifications of Professional Engineer".

#### 1.4 QUALITY ASSURANCE

##### 1.4.1 General

Install Drilled Shaft Foundations in accordance with applicable requirements as described by [ACI 336.1](#) "Reinforced Specifications for the Construction of Drilled Piers", ADSC "Standards and Specifications for the Foundation Drilling Industry", [FHWA-IF-99-025](#) "Drilled Shafts: Construction Procedures and Design Methods" and [FHWA-IP-84-11](#) "Handbook on Design and Construction of Drilled Shafts under Lateral Load".

Submit design data for the following:

- a. [drilled shaft foundation design analysis](#) to include, but not limited to the following:
  1. [Applicable Building code criteria for the geographic area where the excavation will take place](#)
  2. [Dead and Live Loads](#)
  3. [Compressive and Lateral Loads](#)
  4. [Collateral Loads](#)
  5. [Foundation Loads](#)
  6. [Bearing strata](#)
  7. [Casing description](#)
- b. [Mix design data](#) in accordance with the paragraph entitled, "Ready-Mix Concrete"

##### 1.4.2 Sequencing and Scheduling

Submit a detailed installation plan describing the schedule for drilling and/or excavation, installation of steel reinforcement and concrete placement with anticipated site conditions so that each excavated shaft is poured the same day that the drilling is performed.

Submit detailed shop drawings for the following:

- a. [Drilled shaft diameters](#)
- b. [Depth of test holes](#)
- c. [Top and Bottom of shaft elevations](#)
- d. [Steel Reinforcement](#)
- e. [Anchor bolt locations](#)

f. [Accessories](#)

1.4.3 Drilling and Excavation Equipment

Provide drilling and excavation equipment having adequate capacity, including but not limited to, power, torque and down thrust to excavate a hole of diameter and depth indicated. Also provide excavation and over-reaming tools of adequate design, size and strength to perform the work indicated.

Provide special drilling equipment including, but not limited to, rock core barrels, rock tools, air tools and other equipment as necessary to construct the shaft excavation to the size and depth indicated when materials encountered can not be drilled using earth augers and/or over-reaming tools. Submit a list of proposed [excavation and drilling equipment](#).

1.4.4 Construction Criteria

1. Provide and install monolithically cast-in-place concrete drilled shaft foundation to the sizes indicated.

2. Provide and install straight cylindrical shaft foundation of the type indicated.

3. Tolerances:

a. Maximum variation of the center of any shaft foundation from the required location: (3) inches, measured at the ground surface.

b. Bottom Diameter: minus zero, plus (6) inches, measured in any direction.

c. Maximum variation from plumb: 1:40.

d. Maximum bottom level: plus or minus (2) inches.

1.4.5 Inspection Criteria

1. Inspection activities should be designed to minimize delays while insuring the intent of the Industry Standard Specifications.

2. Provide equipment for checking the dimensions and alignment of each shaft excavation. Determine dimensions and alignment jointly with the contractor and engineer. Measure final shaft depths with appropriate weighted tape measure or other approved method after cleaning.

3. A minimum of 50 percent of the base for each shaft is to be less than 1/2 inch of sediment at the time of concrete placement. Maximum depth of sediment or debris at any place on the base of the shaft is not to exceed 1-1/2 inches. Shaft cleanliness is to be determined by the engineer by visual inspection.

1.4.6 Qualification of Excavation Contractor

An experienced excavator with five (5) years experience and licensed in the State of [\_\_\_\_\_] [Florida] who has specialized in excavating and installing work similar in material, design, and extent to that indicated for this Project. Submit certification of the [qualifications of excavator](#).

#### 1.4.7 Qualification of Professional Engineer

Provide engineering services by an authorized engineer; currently licensed in the State of [\_\_\_\_\_] [Florida], having a minimum of four (4) years experience as an engineer knowledgeable in drilled shaft foundation design analysis, protocols and procedures for the [ACI 336.1](#), [FHWA-IF-99-025](#), [FHWA-IP-84-11](#); [ASCE/SEI 7-05](#) and the Florida Building Code 2004 Edition FBC Chapter 18]. Submit certification of [qualifications of engineer](#).

#### 1.4.8 Welding Qualifications

Provide and maintain qualified procedures and personnel according to [AWS D1.1/D1.1M](#), [AWS D1.4/D1.4M](#), [AWS A5.1/A5.1M](#) "Carbon Steel Electrodes for Shielded Metal Arc Welding", [AWS D1.1/D1.1M](#) and "Structural Welding Code--Steel". Submit [welding certificates](#) verifying qualifications for all welding personnel.

#### 1.4.9 Pre-Construction Conference

After submittals are received and approved but before drilled shaft excavation and foundation work, including associated work, is performed, the [Contracting Officer] [Contract Administrator] will hold a pre-construction conference to review the following:

1. The drawings, specifications and the geotechnical report.
2. Finalize construction schedule and verify availability of materials, Excavator's personnel, equipment, and facilities needed to make progress and avoid delays.
3. Methods and procedures related to drilled shaft foundation installation, including engineer's written instructions.
4. Support conditions for compliance with requirements, including alignment between foundation system and erection of structural members.
5. Governing regulations and requirements for, certificates, insurance, tests and inspections if applicable.
6. Temporary protection requirements for foundation assembly during and after installation.

\*\*\*\*\*  
NOTE: Require proof testing if the soundness of  
rock below the caisson bearing level is unknown.  
Indicate location of each caisson to be proof tested.  
\*\*\*\*\*

#### 1.5 PROJECT CONDITIONS

##### 1.5.1 Existing Conditions

Locate existing underground utilities before excavating drilled shaft foundations. If existing utilities are to remain in place, provide protection during drilled shaft operations.

### 1.5.2 Interruption of Existing Utilities

Do not interrupt any utility to occupied facilities unless directed in writing by the [Contracting Officer] [Contract Administrator].

### 1.5.3 Weather Limitations

Proceed with installation preparation only when existing and forecasted weather conditions permit Work to proceed without water entering into the area of excavation.

## PART 2 PRODUCTS

### 2.1 STEEL REINFORCEMENT

#### 2.1.1 Deformed Steel Bars

Steel bars conforming to [ASTM A 615/A 615M](#), Grade 60 ksi and [ACI 318/318R](#).

#### 2.1.2 Plain Steel Wire

Steel wire conforming to [ASTM A 82/A 82M](#).

### 2.2 READY-MIX CONCRETE

Provide ["Ready-Mix Concrete"](#) and Mix Design conforming to [ACI 117](#), [ACI 301](#), and [ACI 304R](#), minimum compressive strength 5,500 psi at 28 days. Slump to be between 5 to 6 inches, according to [ASTM C 143/C 143M](#).

Provide portland cements conforming to [ASTM C 150](#), Type II; provide one brand and type of cement for formed concrete having exposed to view finished surfaces.

Potable water conforming to [ASTM C 94/C 94M](#).

Measure, batch, mix and deliver concrete according to [ASTM C 94/C 94M](#) and furnish batch ticket information.

## PART 3 EXECUTION

### 3.1 PREPARATION

Protect existing structures, utilities, sidewalks, pavements, and other facilities from damage caused by settlement, lateral movement, vibration, and other hazards created by drilled shaft foundation operations.

Provide Fall Protection as required by [29 CFR 1926.501](#), [29 CFR 1926.502](#) and [29 CFR 1926.651](#).

### 3.2 REQUIRED TEST REPORTS

As a minimum, submit the following test reports and data.

- a. [Soils Report](#)
- b. [Ground Water conditions](#)
- c. [Load Test](#)
- d. [Penetration Test](#)
- e. [Slump](#)
- f. [Concrete](#)

g. Compressive Strength

3.3 EXCAVATION

Accomplish excavation of shaft foundations by standard excavation methods including, but not limited to, conventional augers fitted with soil and/or rock teeth, or under-reaming tools attached to drilling equipment of adequate size, power, torque and down thrust necessary for the work.

Excavation is to be performed through whatever materials that are encountered to the dimensions, depths and applicable ACI 336.1 tolerances.

Protect excavated walls with temporary watertight steel casings of sufficient length to prevent water intrusion, cave-ins, displacement of surrounding earth, and injury to personnel and damage to construction operations.

Excavate shafts for drilled foundations to indicated elevations. Remove loose debris, materials and/or muck to make bottom surfaces level within ACI 336.1 tolerances.

Remove water from excavated shaft prior to concrete placement.

3.4 STEEL REINFORCEMENT

Comply with recommendations in the CRSI "Manual of Standard Practice" (CRSI 1MSP) for fabricating, placing and supporting reinforcement. Shop fabricate steel reinforcement in accordance with ACI SP-66.

When practicable to deliver the reinforcement cage assembly to the jobsite as a complete unit ready for installation, should it not be possible make remaining connections and/or splices, as indicated on the approved shop drawings, at-grade level prior to lowering the complete assembly into the hole.

Clean reinforcement of loose rust, mill scale, earth and other foreign materials. Do not tack weld crossing reinforcing bars. Set wire ties with ends directed into concrete, not toward exposed concrete surfaces.

Lower reinforcement steel into the hole in such a manner as to prevent damage to the walls of the excavation; place, tie and/or clip cage symmetrically about the axis of the shaft. Use centering devices securely attached to the cage; to clear the shaft walls and to maintain the cage in place throughout the concrete placement operations.

Cooperate with other trades in setting of anchor bolts, inserts, and other embedded items. Where conflicts occur between reinforcing and embedded items, notify the [Contracting Officer] [Contract Administrator] that conflicts may be reconciled before concrete placement. Anchors and embedded items are to be positioned and supported with appropriate accessories.

Use templates to set anchor bolts, leveling plates and other accessories required for structure erection. Provide blocking and/or holding devices to maintain required anchoring positions during final concrete placement.

3.5 CONCRETE PLACEMENT

Keep all equipment, including but not limited to, mixers, pumps, hoses,

tools and screeds clean and free or set concrete throughout the placement operation.

Convey concrete from the mixer to place of deposit by best industry methods that will prevent segregation and loss of material. Size and design the equipment for conveying concrete to ensure uniform, continuous placement of concrete.

Place concrete in accordance with [ACI 318/318R](#).

Place concrete in a continuous operation and without segregation into dry excavations whenever possible after inspection and written approval by the [Contracting Officer] [Contract Administrator]. Use all practicable means to obtain a dry excavation before and during concrete placement.

Protect freshly placed concrete from premature drying and excessive cold or hot temperatures. When hot weather conditions exist that would impair quality and strength of placed concrete, comply with [ACI 305R](#). Comply with [ACI 306.1](#) for cold-weather protection.

### 3.6 FIELD TESTING

Sample and test concrete for quality control during placement. Quality control testing is provided by the contract. Submit [Bill of Lading for "Ready-Mix Concrete" deliveries](#) to the [Contracting Officer] [Contract Administrator].

Sample freshly placed concrete for testing in accordance with [ASTM C 172](#).

Test concrete for compressive strength at 7 and 28 days for each design mix conforming to [ASTM C 39/C 39M](#) and compression testing in accordance with [ASTM C 31/C 31M](#).

Test Slump at plant for reach design mix in accordance with [ASTM C 143/C 143M](#).

-- End of Section --